# **BV20 Operations Manual**

# **Innovative Technology**

# **Secure Banknote Handling Solutions Of The Future**











# **Revision History**

INNOVATIVE TECHNOLOGY LTD						
Title:	Title: BV20 OPERATIONS MANUAL					
Drawing No	Author	Date		FORMAT		
GA716	MLC	29/07	7/2007	MS Word 2000		
			_			
Issue	Release Date	Modified By		Comments		
Issue 1	15/10/2007	MLC	First Issue			

# **CONTENTS**

1.	INTRODUCTION	5
2.	SCOPE OF DOCUMENT	6
3.	ENVIRONMENT AND POWER REQUIREMENTS	7
4.	GENERAL DESCRIPTION	8
5.	MACHINE INTERFACE: HARDWARE	g
5.1	Interface Connector Pin Details	10
5.2	2 Configuration Button Functions	11
	BV20 Programming Mode	11
	Configuration Card Programming Mode	11
	Current Setting Indicator Mode	11
	Encryption Key Reset Function (CCTALK)	11
5.3	B Additional Hardware Modules	12
	MDB Voltage Regulator Module	12
	110V Voltage Regulator Module	12
6.	MACHINE INTERFACE: PROTOCOLS	16
6.1	Parallel Input and Output:	16
6.2	Pulse Stream Output	17
6.3	Binary Output – BIN	18
6.4	Low Power Option	19
6.5	Serial Input/Output – SIO	21
6.6	S Smiley® Secure Protocol - SSP	24
6.7	Multi-Drop Bus / Internal Communications Protocol (MDB/ICP)	25
6.8	3 CCTalk Protocol – CCT	27
6.9	Other Interfaces available by request from ITL	27
7.	USING BV20 CONFIGURATION CARDS	28
8.	MECHANICAL INSTALLATION	29
9.	ROUTINE MAINTENANCE	30
9.1	Re-Calibration	31
10.	SUPPORT TOOLS	32
10.	.1 Configuration Cards	32

### **BV20 Operations Manual - GA716**

10.2	ITL Bank Note Validator Currency Manager	32
10.3	Validator Programming System (DA3)	32
10.4	Internet Website Support	33
10.5	E-mail Support	33
Аp	pendix A – Exploded Diagrams	34
Аp	pendix B – ESCROW Control	37
Аp	pendix C – Interface Tools DA1 – DA2	38
Аp	pendix D – Configuration Cards	40
Аp	pendix E – PC System Specification	48

#### 1. Introduction

This manual describes the operation of the BV20 Bank note Validator as fitted with Firmware Version 4.00 or greater.

#### **CAUTIONS:**

- THIS PRODUCT MUST BE FITTED WITH A 2 AMP FUSE BEFORE USE.
- THE BV20 VALIDATOR IS PIN FOR PIN COMPATIBLE WITH NV7/8/9/10, BUT NOT PIN FOR PIN COMPATIBLE WITH THE NV2/3/4/4X OR 5 SERIES PRODUCTS.
- DUE TO DIFFERENT NOTE CYCLE TIMES THERE MAY BE TIMING DIFFERENCES FROM THE NV PRODUCTS.

We recommend that you study this manual as there are many new features permitting new uses and more secure applications.

If you do not understand any part of this manual please contact the factory, contact details are below, for assistance. In this way we may continue to improve our product.

Innovative Technology Ltd.

Derker Street Oldham England OL1 4EQ

Tel: +44 (0) 161 626 9999 Fax: +44 (0) 161 620 2090

E-mail: support@innovative-technology.co.uk
Web site: www.innovative-technology.co.uk

#### **WARNING**

ONLY SUITABLY TRAINED PERSONNEL SHOULD CARRY OUT ANY WORK ON THIS EQUIPMENT IN ACCORDANCE WITH ALL CURRENT LOCAL, NATIONAL AND INTERNATIONAL HEALTH AND SAFETY REGULATIONS.

Smiley® and the ITL Logo are international registered trademarks and they are the property of Innovative Technology Limited.

Innovative Technology has a number of European and International Patents and Patents Pending protecting this product. If you require further details please contact the factory.

Innovative Technology is not responsible for any loss, harm, or damage caused by the installation and use of this product. This does not affect your local statutory rights. If in doubt please contact Innovative Technology for details of any changes

### 2. Scope of Document

This document is intended for those who will:

- Install the BV20 equipment. 1.
- Maintain the BV20 equipment. 2.

Although information is included which will allow a degree of fault diagnosis and repair, it is recommended that for all but simple mechanical repairs, the unit must be returned to an approved service centre for repair.

#### **CAUTIONS:**

- NEVER EXCEED THE RECOMMENDED ENVIRONMENTAL AND ELECTRICAL LIMITS.
- DO NOT ATTEMPT TO LUBRICATE THE MECHANISMS AS THIS MAY AFFECT THE NOTE TRANSPORT.
- DO NOT POLISH THE LENS AS THIS MAY ALTER THE OPTICAL CHARACTERISTICS.
- IF THE BV20 VALIDATOR IS DISASSEMBLED THE UNIT MUST BE RE-CALIBRATED AND RE INITIALISED, FOLLOWING RE-ASSEMBLY.

Innovative Technology Ltd has a policy of continual product improvement. As a result the products supplied may vary from the specification described here.

# 3. Environment and Power Requirements

This section details the Environmental and Power requirements.

Environment	Minimum	Maximum	
Temperature	+3°C	+50°C	
Humidity	5%	95% Non condensing	

**Table 1 - Environmental Requirements** 

#### **CAUTIONS:**

- IF THE INPUT VOLTAGE FALLS BELOW 11.5V THE BV20 MAY NOT OPERATE CORRECTLY (WILL REJECT NOTES). THE FRONT BEZEL LIGHTS WILL FLASH TO INDICATE INCORRECT CONDITIONS
- IT IS RECOMMENDED THAT THE POWER SUPPLY USED CAN SUPPLY AT LEAST 1.7 AMPS.

Electrical Supply	Minimum	Maximum
Supply Voltage (V DC) Absolute Limits	+11.5V	+14.2V
MDB IF5 Version Supply Voltage	+18V	+48V DC or 34V AC
Supply Ripple Voltage	0	0.25V @100 Hz
Supply Currents:		
Sleep (Low Power Mode)		1.2mA
Standby		150mA
Validating		540mA
Peak (Motor Stall)		1700mA

**Table 2 - Power Requirements** 

Interface Logic levels	Logic Low	Logic High
Inputs	0V To +0.5V	+3.7 V +12V
Outputs with $2K2\Omega$ pull up	0.6V	Pull up voltage of host interface
Maximum Current Sink	50mA per output	

**Table 3 - Interface Logic Levels** 

### 4. General Description

#### BV20 Validator - the next generation of ITL Bank Note Validators

The BV20 Bank Note System is a compact note-validating machine (see figure 1), suitable for most money machines. It will accept up to 16 different denominations of notes in the serial control mode.




Figure 1 - The BV20 with Vertical Bezels

The BV20 Validator leaves the factory preset to at least one currency so that it is ready for immediate installation. If it is required to change the currency data set this may be done using the PC based Validator Management software.

New currencies and applications are being tested all the time, please refer to our web site or contact the factory for information concerning specific currencies if they are not already included on our approved list.

The BV20 is designed for easy installation in most machines.

Interfacing the Validator is very simple, with the choice of the following protocols:

SSP	PULSE	PARALLEL	BINARY
CCTALK	SIO	MDB	NIS
IF30	IF31	IF32	

Table 4 - Available Interfaces/Protocols

#### 5. Machine Interface: Hardware

The BV20 interface connector is located on the left side of the unit; it has 16 pins (see figure 2) refer to Table 5 for the pin allocation. Two are used for the 0V and +12V power supply and there are five outputs and five inputs, the remaining four pins are reserved for factory use and should not be connected. An example mating connector is Molex type Part No: 39-51-2160.

It is possible to connect the BV20 to machines operating at 110 Volts or to machines operating at MDB voltages by means of additional Hardware modules. The modules are attached to the BV20 by means of the External hardware clips and connected to the 16-pin connector. (See section 5.3)

The BV20 also has a Configuration Button on the opposite side from the Connector (See Figure 3).



Figure 2 - Interface Connector



Figure 3 - Configuration Button

### 5.1 Interface Connector Pin Details

The connector pin details are described below (see table 5); they use an IDC 16-pin 0.1" pitch header with 2 rows of 8 pins.

Pin	Name	Description	
1	Vend 1	Open Collector Output. Function changes depending on Machine Interface Protocol. (See individual interface descriptions for details) Also the Pulse Stream output Also the serial Output pin in SSP Serial Mode, and other serial modes	
2	Vend 2	Open Collector Outputs.	
3	Vend 3	Function changes depending on Machine Interface Protocol.	
4	Vend 4	(See individual interface descriptions for details)	
5	Inhibit 1	Inhibit channel 1 by holding this pin HIGH. To Enable a channel the inhibit must be held LOW Also the serial Input pin in SSP Serial Mode, and other serial modes	
6	Inhibit 2	Inhibit channel 2 by holding this pin HIGH	
7	Inhibit 3	Inhibit channel 3 by holding this pin HIGH	
8	Inhibit 4	Inhibit channel 4 by holding this pin HIGH	
9	Busy	BV20 is validating and stacking output. Active low while the BV20 is reading, transporting or stacking a note.	
10	Escrow	Operate Escrow function by holding LOW (see <u>Appendix B – ESCROW</u> <u>Control</u> for full details)	
11	Factory Use Only	Do Not Connect	
12	Factory Use Only	Do Not Connect	
13	Factory Use Only	Do Not Connect	
14	Factory Use Only	Do Not Connect	
15	+Vin	Nominal 12V DC supply	
16	0V	0V Supply	

**Table 5 - 16 Pin Connector Details** 

#### 5.2 Configuration Button Functions

The functions available via the Configuration Function Button are detailed in Table 6

Configuration Button	Power Status	Function
Press & Hold (> 1 sec)	Powered ON	Sets BV20 to Programming Mode (SSP)
Press Once	Powered ON	Enables Configuration Card Programming
Press Twice (Within Half a second)	Powered ON	Current Setting Indicator
Press & Hold	Powered OFF	Resets Cctalk key to Default setting

**Table 6 – Configuration Button Functions** 

#### **BV20 Programming Mode**

Press and Hold the Configuration Button for at least 1 second whilst the BV20 is powered up. The Bezel LED will flash rapidly to indicate that SSP is being loaded. Once this process has finished the BV20 will reset. The BV20 will now be in Programming Mode (SSP) and allow connection to a PC via a DA1 or DA2 adapter or connection to a DA3.

Note: This mode can only be cancelled by re-programming with a Configuration Card or via the Validator Manager program. Please ensure you are aware of all the BV20 programmed settings before entering this mode. Failure to restore the original setting will stop the BV20 from operating in the Host machine.

#### **Configuration Card Programming Mode**

Press the Configuration Button once whilst the BV20 is powered up. If done correctly the Bezel LED will flash every 1-second. This will allow the insertion of a Configuration Card to change the Firmware Protocol in the BV20. (See Chapter 7<u>- Using BV20 Configuration Cards</u> for full details). This mode can be cancelled by again pressing the Configuration Button once.

#### **Current Setting Indicator Mode**

Press the Configuration Button twice within half a second whilst the BV20 is powered up. The BV20 Bezel LED will then perform a series of flashes to indicate the current settings within the validator. (See Program Check Procedure, **page 2** in Appendix D – Configuration Cards)

#### **Encryption Key Reset Function (CCTALK)**

**Note:** This function will only be possible if the BV20 is programmed to Cctalk mode. It is not possible to reset the key from SSP mode.

Press and hold the Configuration Button Whilst the BV20 powered is off. Apply the power and keep the button pressed for several seconds. The cctalk Encryption key will now be restored to the default setting.

#### 5.3 Additional Hardware Modules

The BV20 currently supports the following additional hardware Modules for connection to machines with alternative power specifications.

#### MDB Voltage Regulator Module.

The MDB Voltage Regulator Module is for use in Vending machines operating at higher DC or AC voltage outputs. The module provides a regulated 12V dc supply to the validator and has Opto isolated inputs and outputs. For further details on the MDB protocol please see chapter 6.7

#### 110V Voltage Regulator Module.

The 110V Voltage Regulator Module allows the BV20 to be used with machines that operate with a 110V AC supply.

The modules attach to the back of the BV20 and are held in place by the expansion port clips and a single fixing screw.

For unit and cable dimensions please see diagrams below.







Figure 4 – BV20 with MDB Voltage Regulator Module Fitted.







#### 6. Machine Interface: Protocols

ITL strongly recommends the use of a Serial protocol (Preferably SSP) to achieve the highest security.

#### 6.1 Parallel Input and Output:

To use Parallel Output for 4-note/channel acceptance the Parallel interface must be programmed into the validator via the Configuration Cards (See <u>Appendix D – Configuration Cards</u>) or via the ITL BNV Currency Manager program.

Vend Signals: (Pins 1 to 4). The four channels have their own individual outputs. If a note is recognised then the relevant Vend line is set low for a period of  $100 \pm 3$ ms. Pulses outside these limits should be rejected as a precaution against false triggering.

**Busy Output:** (Pin 9). This is a general-purpose busy signal. It is active low while the BV20 is in operation.

**Escrow Control:** (Pin 10) Hold this pin Low to enable the single note escrow function. (See <u>Appendix B - ESCROW Control</u>).

If the host machine aborts the transaction by setting the corresponding inhibit input high, the note is returned immediately.

The host machine can force the return of the note to the customer by setting the inhibit line high, at any time before the end of the 30 second time-out. Setting high all the inhibits causes a note reject.

In the event of a note being forcibly removed from the mouth of the BV20 during the 30-second interval, the BV20 will go out of service for 45 seconds.

**Inhibit Operation:** (Pins 5-8) Channel 1 to 4 have their own inhibit input to allow the host machine to refuse specified notes. To inhibit a channel, the relevant inhibit input must be held high. To enable a channel, the corresponding inhibit must be latched low so that notes may be accepted.

If all four inhibits are high simultaneously then the BV20 will be disabled. In this state the bezel LED will not illuminate and if a note is inserted the motor will run in reverse preventing the insertion of the note.

All four inhibits may be connected together to create a 'global' inhibit. In this way the BV20 may be brought in and out of operation by the host machine.

It is possible to operate the BV20 in Low power mode with the Parallel interface. For further details please see Chapter 6.4

#### 6.2 Pulse Stream Output

To use pulse stream output for acceptance of up to 16 note/channel acceptance, The Pulse interface must be programmed into the validator via the Configuration Cards (See <u>Appendix D – Configuration</u> Cards) or via the ITL BNV Currency Manager program.

**Vend Signal:** (Pins 1) When a note is recognised vend 1 will pulse a pre set number of times, the number of pulses can be set via the ITL BNV Currency Manager program (and set to default values with supplied dataset). The pulse width can be set either with the ITL BNV Currency Manager program or via the Configuration Cards (See <u>Appendix D – Configuration Cards</u>)

**Busy Output:** (Pin 9). This is a general-purpose busy signal. It is active low while the BV20 is in operation.

Escrow Control: (Pin 10). No escrow function in this mode

**Inhibit Operation:** (Pins 5-8) Channels 1 to 4 have their own inhibit input to allow the host machine to refuse specified values of notes. To inhibit a channel, the relevant inhibit input must be held high. To enable a channel, the corresponding inhibit must be latched low so that notes may be accepted.

If all four inhibits are high simultaneously then the BV20 will be disabled. In this state the bezel will not illuminate and if a note is inserted the motor will run in reverse preventing the insertion of the note.

Note: Channels higher than four cannot be individually inhibited, but will be globally inhibited if inhibits 1 to 4 are inhibited.

It is possible to operate the BV20 in Low power mode with the Pulse interface. For further details please see Chapter 6.4

#### **Credit Hold Function:**

If this function is enabled in pulse mode by Configuration card or ITL BNV Currency Manager program, the validator will take the note as normal but then wait until the escrow line is toggled low/high before. It will then give out the number of pulses per dollar as set on the programming card. After the pulses have been given, the validator will then wait for another low/high toggle until the full value of credit pulses are given.

For example with a setting of 2 pulses per dollar, a five dollar bill will give 2 pulses, 5 times.

A Typical use of this option would be for a Pool table with a game price of \$1. You could insert a \$5 note and press a button that toggles the escrow line and releases the pool balls, this would then allow you to play the first game. The Validator holds onto the remaining credits until the game has finished and the button is pressed again allowing the next game to begin, this continues until all the credits have been used.

The busy line remains low throughout the whole process and the validator remains inhibited until all pulses are given.

#### 6.3 Binary Output - BIN

To use Binary mode The Binary interface must be programmed into the validator via the Configuration Cards (See <u>Appendix D – Configuration Cards</u>) or via the ITL BNV Currency Manager program.

In the event that the machine needs more than 4 notes to be recognised, but the host machine cannot take advantage of the serial communication methods then the BV20 can be set to give a binary pattern output on the four parallel output pins.

If the BV20 is set to binary mode it will issue the vend signals as a binary pattern on the parallel outputs for  $100 \pm 3$ ms. In this way a maximum of 15 different notes can be accepted and 4 notes individually inhibited.

**Vend Signals:** (Pins 1 to 4). The four channels have their own individual outputs. If a note is recognised the binary representation of the channel number will be pulled low for  $100 \pm 3$ ms. Pulses outside these limits will be rejected as a precaution against false triggering due to noise.

**Busy Output:** (Pin 9). This is a general-purpose busy signal. It is active low while the BV20 is in operation.

**Escrow Control:** (pin 10). Hold this pin Low to enable the single note escrow function. (See Appendix B – ESCROW Control).

If the host machine aborts the transaction by setting the corresponding inhibit input high on pin 10, the note is returned immediately.

The host machine can force the return of the note to the customer by setting the inhibit line high, at any time before the end of the 30 second time-out. Setting all the inhibits high causes a note reject.

In the event of a note being forcibly removed from the mouth of the BV20 during the 30-second interval, the BV20 will go out of service for 45 seconds.

**Inhibit Operation:** (Pins 5-8) **C**hannels 1 to 4 have their own individual inhibit input to allow the host machine to refuse specified values of notes. To inhibit a channel, the relevant inhibit input must be held high. To enable a channel the corresponding inhibit must be latched low so that notes may be accepted.

If all four inhibits are high simultaneously then the BV20 will be disabled. In this state the bezel will not illuminate and if a note is inserted the motor will run in reverse preventing the insertion of the note.

Note: Channels higher than four cannot be individually inhibited, but will be globally inhibited if inhibits 1 to 4 are inhibited.

It is possible to operate the BV20 in Low power mode with the Binary interface. For further details please see Chapter 6.4

#### 6.4 Low Power Option

#### Notes:

- Low Power Mode can ONLY be used with the above Parallel, Pulse and Binary protocols.
- Low power mode can only be enabled by correctly completing the configuration cards or via the ITL BNV Currency manager program.
- In Low Power Mode the front sensor is checked every 1 second which can lead to a
  delay in accepting the note when it is presented.
- Configuration button functions are only available during power up before the BV20 goes into Low Power mode

Electrical Supply	Minimum	Maximum
Supply Voltage (V DC) Absolute Limits	+11.5V	+14.2V
MDB IF5 Version Supply Voltage	+18V	+48V DC or 34V AC
Supply Ripple Voltage	0	0.25V @100 Hz
Supply Currents:		
Sleep (Low Power Mode)		1.2mA
Standby		150mA
Validating		540mA
Peak (Motor Stall)		1700mA

Low power Mode can be used with all none serial communication protocols to reduce the power consumption of the BV20 when idle. When the BV20 is in this state the current consumption is reduced to approximately 1.2mA. The BV20 goes into low power mode approximately 4 seconds after the validator is powered up and remains in this state until a note is entered (Time A). Following a note insertion the BV20 returns to Low Power mode approximately 1 second after the Busy line goes High (After credit is given or note is rejected). (Time B)

Low Power mode uses 3 control lines: Vend - Pin 1, Inhibit - Pin 5 and Busy - Pin 9




Figure 11 - Low Power Mode Timing Diagram

#### **BV20 Operations Manual - GA716**

#### TIMING DIAGRAM EXPLAINATION

When the Validator is enabled the Inhibit line is Low and the Busy line is High. This remains the same until a note is inserted (Time A)

When a note is inserted under the front sensor the BV20 wakes up and the busy line goes low to indicate that the validator is in use. The busy line remains low during the validating and stacking process and once the note has been successfully validated and stacked the vend line goes low to issue the credit.

After the credit is issued the busy line goes high and approximately 1 second after the busy line goes high (Time B) the BV20 goes back into low power mode.

#### 6.5 Serial Input/Output – SIO

Existing Smiley® NV4 -NV10 users may already be using the serial input/output facility in conjunction with the parallel inputs. The BV20 Validator also supports this system. However this interface is not recommended for new designs, the Smiley® Secure Protocol SSP interface is recommended.

#### **CAUTION:**

- THE BV20 <u>DOES NOT</u> SUPPORT THE SIMPLE SERIAL DATA OUT ONLY MODE AS AVAILABLE ON NV4 AND EARLIER MODELS NV2 AND NV3. IT ONLY SUPPORTS THE SERIAL DATA INPUT/OUTPUT MODE.
- THE HOST MACHINE <u>DOES NOT</u> ECHO MESSAGES BACK TO THE VALIDATOR.
- THE BV20 <u>DOES NOT</u> OPERATE IN TRUE RS232 MODE. (ONLY TTL LEVEL).

To use Serial Input/Output mode The SIO interface must be programmed into the validator via the Configuration Cards (See <u>Appendix D – Configuration Cards</u>) or via the ITL BNV Currency Manager program.

There are 4 different combinations of SIO available

SIO 300 Baud

SIO 300 Baud (Disabled at Start up) - A software enable must be sent to enable the validator.

SIO 9600 Baud

SIO 9600 Baud (Disabled at Start up) - A software enable must be sent to enable the validator.

The data is formatted as follows for 300 Baud

#### 1-start bit - 8 data bits - 2 stop bits




Figure- 4 Typical Serial Output: Transmission of the value 20 (decimal), Note not recognized

The data is formatted as follows for 9600 Baud

#### 1-start bit - 8 data bits - 1-stop bits




Figure- 5 Typical Serial Output: Transmission of the value 20 (decimal), Note not recognized

The BV20 will receive and transmit the following event codes:

Recognised Receive Codes to BV20		Transmitted codes from BV20		
MESSAGE	DECIMAL VALUE	MESSAGE	DECIMAL VALUE	
Inhibit C1	131	Note Accept on C1	1	
Inhibit C2	132	Note Accept on C2	2	
Inhibit C3	133	Note Accept on C3	3	
Inhibit C4	134	Note Accept on C4	4	
Inhibit C5	135	Note Accept on C5	5	
Inhibit C6	136	Note Accept on C6	6	
Inhibit C7	137	Note Accept on C7	7	
Inhibit C8	138	Note Accept on C8	8	
Inhibit C9	139	Note Accept on C9	9	
Inhibit C10	140	Note Accept on C10	10	
Inhibit C11	141	Note Accept on C11	11	
Inhibit C12	142	Note Accept on C12	12	
Inhibit C13	143	Note Accept on C13	13	
Inhibit C14	144	Note Accept on C14	14	
Inhibit C15	145	Note Accept on C15	15	
Inhibit C16	146	Note Accept on C16	16	
Un-inhibit C1	151	Note Not Recognised	20	
Un-inhibit C2	152	Mechanism running slow	30	
Un-inhibit C3	153	Strimming attempted	40	
Un-inhibit C4	154	Channel 5 Note Rejected (fraud channel)	50	
Un-inhibit C5	155	STACKER Full or Jammed	60	
Un-inhibit C6	156	Abort During Escrow	70	
Un-inhibit C7	157	Note may have been taken to clear jam	80	
Un-inhibit C8	158	Validator Busy	120	
Un-inhibit C9	159	Validator Not Busy	121	
Un-inhibit C10	160	Command Error	255	
Un-inhibit C11	161			
Un-inhibit C12	162			
Un-inhibit C13	163			
Un-inhibit C14	164			
Un-inhibit C15	165			
Un-inhibit C16	166			
Enable serial escrow mode	170			
Disable serial escrow mode	171			
Accept Escrow	172			
Reject Escrow	173			
Status	182			
Enable all	184			
Disable all	185			
Disable escrow timeout	190			
Enable escrow timeout	191			

**Table 7 - Receive and Transmit Codes** 

### **BV20 Operations Manual - GA716**

Example transactions are shown below (see table 8):

Event Validator		Decimal Value	Host
Note entered into validator	Validator Busy	120 <del>&gt;</del>	
Note Accepted Channel 2	Validator Ready	121 <del>&gt;</del>	
	Accept on Channel 2	2 →	
Note entered into validators	Validator Busy	120 <del>&gt;</del>	
Note not recognised	Validator Ready	121 <del>&gt;</del>	
	Note not recognised	20 →	
Validator has returned note	Validator Ready	121 <del>&gt;</del>	
Software Inhibit Channel 4	Inhibit C4	<b>←</b> 134	Inhibit C4
	Channel 4 Inhibited	134 <del>&gt;</del>	
Software Enable Channel 4	Uninhibit C4	<b>←</b> 154	Uninhibit C4
	Channel 4 Inhibited	154 <del>&gt;</del>	
Status Report		<b>←</b> 182	Status Request
	Status Requested	182→	
3 byte status message	Inhibit status Channels 1-8	Byte 1→	
	Inhibit status Channels 9-	Byte 2→	
	Escrow On (=1) / Off (=0)	Byte 3 <b>→</b>	
Turn on Escrow Mode		<b>←</b> 170	Enable Escrow
	Escrow Mode Enabled	170 →	Mode
Note accept in Escrow Mode			
Note entered into validator	Validator Busy	120 <del>&gt;</del>	
Note Accepted Channel 2	Validator Ready	121 <b>→</b>	
	Accept on Channel 2	2 <b>→</b>	
		<b>←</b> 172	Accept Note in Escrow
	Accept Escrow	172 <b>→</b>	
	Accept on Channel 2	2 <b>→</b>	

**Table 8 - Example Protocols** 

#### 6.6 Smiley® Secure Protocol - SSP

NOTE: Please refer to the Smiley® Secure Protocol (SSP) Specification (ITLDrawing GA138) on the web site for full details of the SSP protocol.

To use SSP mode The SSP interface must be programmed into the validator via the Configuration Cards (See <u>Appendix D – Configuration Cards</u>) or via the ITL BNV Currency Manager program, or by pressing and holding the Configuration Button for more than 1 second.

SSP is a secure serial interface specifically designed to address the problems experienced by cash handling systems in gaming machines. Problems such as acceptor swapping, reprogramming acceptors and line tapping are all addressed. This interface is recommended for all new designs.

The interface uses a master slave model, the host machine is the master and the peripherals (note acceptor, coin acceptor or coin hopper) are the slaves.

Data transfer is over a multi-drop bus using clock asynchronous serial transmission with simple open collector drivers. The integrity of data transfers is ensured through the use of 16 bit CRC checksums on all packets.

Each SSP device of a particular type has a unique serial number; this number is used to validate each device in the direction of credit transfer before transactions can take place.

Commands are currently provided for coin acceptors, note acceptors and coin hoppers. All current features of these devices are supported.

#### Features:

- Serial control of Note / Coin Validators and Hoppers
- 4 wire (Tx, Rx, +V, GND) system
- RS232 (TTL) open collector driver
- High Speed 9600 Baud Rate
- 16 bit CRC error checking
- Data Transfer Mode

#### Benefits:

- Proven in the field
- Simple and low cost interfacing of transaction peripherals.
- High security control of payout peripherals.
- Defence against surrogate validator fraud.
- Straightforward integration into host machines.
- Remote programming of transaction peripherals
- Open standard for universal use.

For detailed information and full protocol specification please refer to SSP Interface Specification ITL (Drawing GA 138), this is available from the ITL website www.innovative-technology.co.uk.

To help in the software implementation of the SSP, ITL can provide DLL controls and Visual Basic applications on request. Please contact



#### 6.7 Multi-Drop Bus / Internal Communications Protocol (MDB/ICP)

To use the MDB mode an MDB Voltage Regulator Module should be fitted to the BV20 Expansion port or alternatively an IF5 interface box can be used. The MDB interface must be programmed into the validator via the Configuration Cards (See <a href="Appendix D - Configuration Cards">Appendix D - Configuration Cards</a>) or via the ITL BNV Currency Manager program,

#### Note:

- Please refer to the Multi-Drop Bus specification for the suggested current drive circuits available.
- The BV20 supports the MDB protocol version 1, level 1
- For detailed information and full protocol specification please refer to www.vending.org

MDB defines a serial bus interface used in electrically controlled vending machines (see figure 6). This is a 9600 Baud Master-Slave system where the BV20 banknote validator is a slave to a master controller. A master has the capability of communicating with 32 peripherals or slaves. The master is defined as the Vending Machine Controller (VMC).




Figure 6 - MDB Opto Isolated Input / Output circuits BV20 MDB Slave

The BV20 banknote Validators have a unique address – 00110XXX binary (30H). The VMC polls the bus to detect presence of the BV20 Validator or get information on the current status of the Validator.

The Validators will respond when asked for activity with an acknowledgment, a negative acknowledgment or a specific reply, depending on its current status. Bus crashes are avoided as the Validators respond to being polled only by the VMC.

The international country code must be set for the country in which the Validators will be operating. This is either the international telephone code for that country, or the country code taken from ISO4217. The code is represented as two bytes. The initial digit signifies the source of the code. 0 signifies the telephone code is used, 1 signifies ISO4217 has been used.

For the USA the country code is 00 01, or 18 40

For Great Britain the code is 00 44, or 18 26.

The scaling factor must also be specified for each Validator. All accepted note values must be evenly divisible by this number.

- This number would be set to 100 (Hex 64) for the Euro or Great Britain.
- The number would be set to 1000 (Hex 03E8) for Columbia.
- The number of decimal places must also be programmed for each Validator
- The number would be set to 2 for Euro or USA
- The number would be set to 3 for Columbia



#### **BV20 Operations Manual - GA716**

Adopting the numbers above:

- £5 would be displayed as 5.00
- £10 would be displayed as 10.00
- \$1 would be displayed as 1.00
- 1K Columbia would be displayed as 1.000

#### 6.8 CCTalk Protocol – CCT

The BV20 supports the CCTalk serial protocol for easy interfacing with host machines that support this protocol.

To use CCTalk mode The CCT interface must be programmed into the validator via the Configuration Cards (See <u>Appendix D – Configuration Cards</u>) or via the ITL BNV Currency Manager program,

Pin out connections on BV20 for CCTalk are shown below (see figure 7) looking at the connection pins on the BV20 interface connector as defined in the CCTalk specification. It is recommended that all communications with the note validator must be encrypted using the encryption key, the default encryption key will be printed on the label of the BV20. To reset the Encryption key to it's default value see Chapter 5.2.

NOTE: For detailed information and full protocol specification please refer to www.CCTalk.org




Figure 7 - CCTalk Connection Pins on the BV20

#### 6.9 Other Interfaces available by request from ITL

- NIS Compatible with Mars Non-Isolated Serial Protocol
- IF30 Compatible with ID003 protocol
- IF31 Special interface (Columbia)
- IF32 Compatible with Cash Code CCnet Protocol

## 7. Using BV20 Configuration Cards

The Configuration Cards offer the following functions:

- Select required Communication Interface (SSP, Cctalk, Parallel etc).
- Adjust the channel and pulse configuration on a pre-programmed BV20 to your own requirements.

Programming the BV20 with the configuration cards is enabled via the 'Configuration Button' on the right hand side of the BV20 (see Chapter 5.2 <u>Configuration Button Functions</u>. (For details on how to complete the configuration cards please see <u>Appendix D – Configuration Cards</u>)


- 1) Press the Configuration button Once whilst the validator is powered up.
- 2) The Green bezel LED will now flash with a steady heartbeat until a Configuration Card is entered.
- 3) Once the Configuration Card has been entered the validator reads the card and immediately returns it.
- 4) The LED then flashes rapidly whilst the interface is being changed. If the LED flashes a number of times slowly, it is an indication of an error (For details of the Error Flash codes please see page 1 of Appendix D Configuration Cards
- 5) When the changes are complete the validator resets.

If a configuration card is not entered, this function can be cancelled by pressing the button again. Once

It is now possible to check the programmed settings of the BV20 by pressing the Configuration button twice within half a second. (For details see page 2 of <u>Appendix D – Configuration Cards</u>)

# 8. Mechanical Installation

The BV20 validator is available with either a 66mm or 72mm Bezel.



#### 9. Routine Maintenance

The BV20 Validator has been designed to minimise any performance variation over time. Much of this is achieved by careful Hardware and Software design.

However, depending upon the environment in which it is used the BV20 may at some time require re-calibration.

#### 9.1 **Re-Calibration**

The BV20 has an in-built self-calibration system that maintains the optical sensors at their best operating point. However if the BV20 is disassembled for any reason it will need to be re-calibrated. Re-calibration may only be performed under license from ITL, contact support@innovativetechnology.co.uk for further details.

This can be performed in conjunction with the diagnostics software option in the ITL BNV Currency Manager Program and help menus supplied with this program.

### 10. Support Tools

The following support tools are available for use with the BV20 Bank Note Validator:

- ITL Bank Note Validator Currency Manager Software.
- · Configuration Cards.
- Validator Programming System (DA3)
- Downloads from the Innovative Technology Ltd website: www.innovative-technology.co.uk
- E-mail Support via <a href="mailto:support@innovative-technology.co.uk">support@innovative-technology.co.uk</a>

#### 10.1 Configuration Cards.

For full details of the use and function of the Configuration Cards please see Appendix D – Configuration Cards

#### 10.2 ITL Bank Note Validator Currency Manager

NOTE: The Validator must be set to Programming Mode (SSP) when connected to a computer or DA3 and then returned to the original Settings when complete (See Chapter 5.2 Error! Reference source not found.).

ITL BNV Currency Manager 3.2.0 or Higher must be used to access the BV20 functions

The ITL BNV Currency Manager software offers the following functions:

- Program the Validator by downloading pre-prepared currency data via the DA1 or DA2 kit.
- Check the firmware version and currency set already loaded on a BV20 unit.
- Adjust the channel and pulse configuration on a pre-programmed BV20 to your own requirements.
- Download a new version of firmware onto the BV20.
- Use diagnostic functions to check Validators operation

The software will run on an IBM compatible Personal Computer with Pentium<sup>™</sup> processor or equivalent (see <u>Appendix E – PC System Specification</u> for operating system requirements) and requires a DA1 kit fitted to the serial port or DA2 kit fitted to the USB port. (See <u>Appendix C – Interface Tools DA1 – DA2</u>)

#### 10.3 Validator Programming System (DA3)

The DA3 is a programming system designed to enable the programming of ITL Bank Note Validators in the field without the use of a PC.

Once the DA3 has been programmed the user can:

- Update the existing software within a validator to the latest versions using the BNV Match Download function.
- Test the functionality of the validator away from the Host machine.

For full DA3 operation and functionality details please refer to the DA3 User Manual (Document number GA339)

Note: The BNV Overwrite download function is not available for the BV20 due to the Firmware/Dataset file structure



#### **BV20 Operations Manual - GA716**


#### 10.4 **Internet Website Support**

The Innovative Technology Ltd website provides the means to download new and updated currency sets and new versions of firmware for the BV20. You can obtain these along with technical bulletins by visiting www.innovative-technology.co.uk

#### 10.5 **E-mail Support**

If the data you require is not available over the Internet Innovative Technology supports an e-mail system to help customers with unusual requirements. The address is: support@innovative-technology.co.uk

# Appendix A – Exploded Diagrams



# **BV20-1 Operations Manual**

# **Exploded Diagram Parts List**

N0	Part No	Part Description	Qty
1	PM771	BV20 Case	1
2	PM770	Bezel 72mm	1
2	PM781	Bezel 66mm	1
3	PA775	66mm Lens Assembly	1
3	PA776	72mm Lens Assembly	1
4	PM787	Light Pipe	1
5	PM775	Pressure Wheel	3
6	SP162	Axle Spring	3
7	PA771	Front Axle Assembly	1
8	PM774	Idle gear (16T – 0.8M)	1
9	SC113	No.4 20x1/4" Pozi Flange BZP	1
10	PB243	Printed Circuit Board	1
11	PM773	Motor Cover	1
12	PA774	Motor Assembly	1
13	PA773	Drive Axle Assembly	1
14	MC253	Gear Shaft	1
14	PM533	Helical Compound Gear	1
14	PM772	Compound Gear	1
15	LB155	Strim Sensor Label	1

### Appendix B - ESCROW Control

The BV20 has a single note escrow facility (pin 10) used in Parallel and Binary modes. This allows the Validator to hold onto the note once accepted, and then only stack the note in the cash box when the host machine confirms that the Vend operation has been completed. If no confirmation of the Vend is received then the note will be returned to the customer after 30 seconds, (see figure 8).




Figure 8 - Escrow Timing Diagram for Parallel Vends

If the host machine itself aborts the transaction by setting the corresponding inhibit input high, the note is returned immediately. The sequence of operations is as follows:

- Pin 10 held low awaiting note insertion.
- Note inserted. Validator issues a 100ms pulse on the appropriate channel.
- The host machine initiates vend process.
- The host machine sets pin 10 high to indicate that it wants the note. If this is not done within 30 seconds the Validator will return the note.
- The Validator issues a 100ms pulse on the appropriate channel after pin 10 going high to indicate final acceptance of the note. If the signal has not been received within 30 seconds it indicates the customer has forcibly retrieved the note and the vend will be aborted.
- The vend process is completed.
- The host machine sets pin 10 low in expectation of the next vend.

The host machine can force the return of the note to the customer by setting the inhibit line high, at any time before the end of the 30 second time-out. For channels above 4, setting all the inhibits high will cause a note reject.

In the event of a note being forcibly removed from the mouth of the BV20 during the 30-second interval, the BV20 will go out of service for 45 seconds.

### Appendix C - Interface Tools DA1 - DA2

The DA1/2 Kits are designed for the following:

- Connecting of ITL Note Validators to a PC for the upgrade and user option setting of Currency and Firmware files.
- Testing note acceptance of Note Validators independent of the host machine to confirm that the validator is working.

The DA1and DA2 Kits comprise the following components:

DA1	DA2				
DA1 adapter board	DA2 adapter board				
DA1 to NV7-10 and BV cable	USB type-A to Type-B cable				
DA1 to NV4 Cable	DA2 to NV7-10 and BV cable				
Power Cable	Power Cable				
ITL Support CD-ROM	ITL Support CD-ROM				

### Connecting a DA1 to a validator and PC

For the PC system specification and set up refer to Appendix E – PC System Specification.

Connect the DA1 to the validator as shown below (see figure 9), using the 16-way to 5-way connector. The supplied 3.5mm jack plug and 2 banana plugs are used to supply power to the DA1 when using a variable Bench power supply (Connect the +12 volts to the red banana plug and GND (0V) to the black plug). Alternatively a Portable DC Power Adapter supplying 12v and 1.5A minimum can be used.

Plug the 9-way D-type connector into the serial port of the PC and note of the number of the port, as this will be needed later for configuring the software. Once the connections have been made install the appropriate software for the validator you are using.

NOTE: The Validator must be in Programming mode when connected to a computer and then returned to the Original Settings when the download is complete




Figure 9 - Connecting DA1 to BV20 and PC for upgrading Validator programs

### Connecting a DA2 to a validator and PC




Figure 10 - Connecting DA2 to a BV20 and PC for upgrading Validator Programs

#### **Software Installation**

DA1 - To install the ITL BNV Download Manager Software insert the CDROM into the correct PC drive. The CD should automatically run and an installation menu will appear. Double click the ITL BNV Download Manager and follow the on-screen instructions. You can also install the Currency files, Firmware files and the Technical Manuals for each specific product as well as other generic documentation.

The Quick Start Guide for the DA1 is Document number GA151.

DA2 - To install the ITL BNV Download Manager Software insert the CDROM into the correct PC drive. The CD should automatically run and an installation menu will appear. Double click DA2 installation guide (GA338) and follow the instructions relating to your specific Operating System.


NOTE: All files contained on the CD are available from the ITL Website: http://www.innivative-technology.co.uk

Please contact <a href="mailto:support@innovative-technology.co.uk">support@innovative-technology.co.uk</a>, if you require further assistance.

## **Appendix D – Configuration Cards**

# **GA 713 BV Configuration Option Progamming**





### Instructions for use

- 1 Cut card around outline check measurements as printed. Check print options 'Page scaling' is set to 'None' when printing a pdf file to ensure correct size.
- 2 Fill in sections as required. Take care to fill in the sections correctly, keep inside the lines and fill boxes fully as example below:



- 3 Power-up BV and allow to reset.
- 4 Click 'Function' button on BV to access Configuration Mode, BV bezel LEDs should be flashing at 1 second interval.
- 5 Enter card into BV in direction indicated by arrows.
- 6 Card will be rejected and if configuration was good the, bezel LEDs will flash at a fast rate while programming takes place. TAKE CARE TO ENSURE THE POWER IS NOT REMOVED AT THIS STAGE, THE BV MAY SUFFER PERMANENT DAMAGE!! The BV will then reset.
- 7 If an error has occurred, the card will be rejected and the bezel LEDs will flash slowly a number of times to indicate the error cause. (See table below for codes).

# 8 - IMPORTANT - CHECK THAT THE CONFIGURATION REQUESTED HAS BEEN SET IN THE BV BEFORE USE!

Flash	Error
2	Invalid card read - card entered wrong way round, card mis-read or card wrong version.
3	No interface selection was detected on card.
4	Multiple interface selection detected.
5	Invalid interface selected - the selected interface is not available for this BV.
6	Selected interface not compatible with BV version.
7	Pulse configuration error. Selected pulse options invalid.(e.g. multiple pulse per dollar)
8	ccTalk configuration error. Selected cctalk options invalid. (cctalk 8 bit chk not allowed without ccTalk Plain.)

Low power mode not available on this BV version.

9

## **Program Check Procedure**

To check settings on a programmed unit:

- 1 Power on unit.
- 2 Click program set button on unit twice (like double click on mouse).
- 3 Monitor bezel led and check flash codes on table below

_	Flash count	Pulse High	Pulse Low	Pulse per dollar	High speed	Disabled	cctalk plain	cctalk 8 bit	low power	binary	Credit Hold
SSP	1										
Pulse	2	ms/10	ms/10	value							3 flash
MDB	3										
IF 30	4										
IF 31	5										
cctalk	6						1 flash	2 flashes			
SIO	7				1 flash	2 flashes					
Parallel	8									1 flash	
spare	9										
NIS	10										
IF 32	11				1 flash						
spare	12										
spare	13										
spare	14									· ·	

#### For example:


A pulse inteface with 50ms high, 100ms low, 2 pulse per dollar will flash as follows 2,5,10,2

A SSP interface will only ever flash once

A cctalk interface with 16 bit checksum, no encryption wil flash 6,1


A cctalk interface with 8 bit checksum, no encryption wil flash 6,1,2

A Binary interface will flash 8,1




Below are some typical examples of completed Configuration Cards.


Note: These Configuration Cards are samples and should not be copied for programming use. Please see document GA713 for useable cards.




### **BV20 Operations Manual - GA716**



### **BV20 Operations Manual - GA716**



### **BV20 Operations Manual - GA716**



## Appendix E - PC System Specification

The ITL Validator Software has been tested and verified using Windows 2000/XP/Vista <sup>tm</sup> on a Pentium <sup>tm</sup> based PC System (© Microsoft and Intel). Full functionality cannot be guaranteed on lower specification systems.